### **Generation X Study**

### Mechanical



Dave Peters George T. Roach

July 27, 2000



### Mechanical Topics

- Overview
- Driving Requirements and Assumptions
- Options considered
- Selected Configuration and Rationale
- Spacecraft Configurations
- Mass Summary
- ◆ Trades / Risks / Issues & Concerns



### Mechanical Overview

- ♦ Several options/configurations have been studied.
- ♦ Each have their merits depending on baseline assumptions.
- ♦ Each will be presented, their advantages and disadvantages will be discussed.



# Mechanical Driving Requirements

### **♦ Challenge:**

- Design next generation X-Ray telescope that
  - Has 25 M<sup>2</sup> collector (mirror) area.
  - Has a 100 M focal length
  - Provide S/C bus to house power, comm, ACS, C&DH.
- Launch scenario:
  - Direct insertion to L2 orbit
  - Insertion of components to LEO (space station), assembly at station, transfer to L2 orbit



### Mechanical Selected Configuration and Rationale

- ◆ Because the study is just beginning all configurations were considered.
- ♦ Some were dismissed quickly for obvious reasons.
- **♦** The others have their merits that warrant further study.
  - These options/configurations will be presented with their advantages and disadvantages




### \*

#### Option #1

- Direct insertion to L2
- Petals fold down around Bus
- •Mast deploys to 100 M
- •Will dimensionally fit in Delta IV shroud

#### Rejected

• Thermal limitations -Petals present too much exposed area for adequate thermal control







#### Option #2

- Direct insertion to L2
- •Delta IV launch vehicle
- •6 Petals
- Spinner, S/C bus despun
- Solar array
  - Deployed from end of collectors
- •Mast deploys to 100 M

#### Rejected:

- Does not meet 25 M<sup>2</sup>
- Thermal limited










### Option #3

- Components to LEO
- Assembly and Check-out at Space Station
- Collector segments form 6 M dia.
- Solar array around collector. Also serves as sun shade for collector
- Spinner with despun bus
- Mast deploys to 100 M
- Component size will be optimized for launch vehicle

#### **Draw-backs**:

- Means of transfer to L2
  - · Slow trip-
    - long dwell in radiation belt
    - soft ride
  - Quick trip-
    - chance of damage to collector
    - misalignment of collector








#### Option #4


- Direct insertion to L2
- Delta IV launch vehicle
  - mass critical!!
- 3 Modules
  - · 2 collectors 4M dia. each
  - 1 bus 4M dia.
- Modules will rotate and drop into place
- Solar array
  - deployed from side of bus
  - along surface of collectors
- Mast deploys to 100 M


#### Draw-backs:

- Mass Critical
- If shuttle is used no provisions have been made for apogee kick motor for L2 insertion



#### Stowed









#### Option #5

- Direct insertion to L2
- •Delta IV launch vehicle
- •4 Petals
- Solar array
  - •along surface of collectors
- •Mast deploys to 100 M
- Apogee kick motor incorporated

#### **Draw-backs**:

Thermally challenging







### Mechanical Mass Summary

◆ Capabilities		♦ S/C Mass	
<ul> <li>Delta IV (heavy)</li> <li>LEO -</li> <li>C3 = -0.7 -</li> </ul>	20,500 kg 7526 kg	<ul><li>Experiment</li><li>Bus</li><li>Sub-systems</li></ul>	5600 kg 500 kg 500 kg
<ul><li>Atlas V (552)</li><li>LEO</li><li>C3 = -0.7 -</li></ul>	20,520 kg 5719 kg	• Prop system (LEO to L2) (Star 63F)	5000 kg
<ul><li>STS (shuttle)</li><li>LEO -</li></ul>	<u>12,000</u> 14,000 kg		



### Mechanical Trades/Risks/Issues & Concerns

♦ Option #1

**REJECTED (Thermal)** 

♦ Option #2









- plus symmetrical, thermal friendly, large solar array
- minus EVA involved, propulsion required





- plus large collector area, lower inertia, adjustable alignment
- minus complex deployment, mass

♦ Option #5



- plus simpler deployments, symmetrical
- minus thermally challenging, sun shielding